



# QUOTE

Mike Page

**Date**  
27 Aug 2025

**Expiry**  
26 Sep 2025

**Quote Number**  
QU-0056

**Reference**  
Memorial scupper drain

**GST Number**  
59-948-776

Eben Sinclair Pool and  
Repair services  
1/4 Links Ave  
Mt Maunganui 3116  
NEW ZEALAND  
ebensinclair@gmail.com  
027 287 5835

## Memorial Pool pipework replacement on lap pool

- To replace the pipework on the scupper drains on the lap pool at memorial.
- Connect into the existing 200mm cast iron pipe close to the pool.
- Epoxy mortar/ seal the 100mm take offs in scupper drain
- epoxy mortar any redundant holes or suspect places water may leak from.
- will need to empty pool to get access to the scupper drains properly.

Description	Quantity	Unit Price	Amount NZD
150mm PVC pressure pipe 6m lengths	12.00	775.20	9,302.40
100mm PVC pressure pipe 6m lengths	2.00	477.60	955.20
150mm PVC T	7.00	163.20	1,142.40
150mm 90 degree	1.00	142.40	142.40
150mm x 100mm reduce bush	6.00	117.98	707.88
100mm PVC elbows	2.00	62.23	124.46
100mm 45 degree elbows	6.00	64.30	385.80
Possible 200mm pipe needed- various other fittings to allow for. gib bolt, 200mm T. Wont know untill we view best way to do it,	1.00	1,600.00	1,600.00
epoxy mortar, PVC glue and primer, concrete bags.	1.00	450.00	450.00
Labour - approx 2 weeks	80.00	70.00	5,600.00
		Subtotal	20,410.54
		TOTAL GST 15%	3,061.58
		<b>TOTAL NZD</b>	<b>23,472.12</b>

**Terms**

---

Quote valid for 30 days following date on this quote.